


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 34 Twp. 21 Rge. 13 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW
Lease Owner Petroleum, Inc.
Lease Name McCoy Well No. 1
Office Address 100 Derby Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 21, 19 51
Application for plugging filed May 21, 19 51
Application for plugging approved May 21, 19 51
Plugging commenced May 21, 19 51
Plugging completed May 21, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives
Producing formation Depth to top Bottom Total Depth of Well 3771 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 240'. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 35'. Placed wooden plug at 35' and 1/2 sack of Hulls on top of plug. Filled hole to bottom of cellar with 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1951 5-25-51
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 19 51
Charlotte Weidman
Notary Public.

My commission expires October 13, 1954

23-5091-S 8-50-10M

PLUGGING
FILE SEC 34 T 21 R 13 W
BOOK PAGE 82 LINE 40

WELL LOG McCOY #1

Petroleum, Inc., Lease Owner

Section 34, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: SW SW NW

Rotary Total Depth: 3771'

County: Stafford

Commenced: May 8, 1951

Elevation: 1891 R.B.

Completed: May 21, 1951

Production: D & A

Casing: 243' of 8 5/8"

Figures below indicate bottom of formation:

60	Clay & Sand		
170	Sand & Gravel		
222	Sandstone	3227	Heebner
243	Blue Shale & Shells	3359	Brown Lime
290	Shale	3372	Lansing
735	Red Bed	3597	B.K.C.
765	Anhydrite	3611	Conglomerate
1520	Shale & Shells	3656	Viola
2300	Lime & Shale	3692	Simpson
2750	Shale & Shells	3746	Arbuckle
3005	Lime & Shale		
3274	Lime		
3358	Lime & Shale		
3617	Lime		
3654	Lime & Shale		
3656	Conglomerate		
3695	Chert		
3746	Shale		
3771	Lime		

Tops:

3771' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

RECORDED
STATE CORPORATION

PETROLEUM, INC.

STATE OF KANSAS)
COUNTY OF SEDGWICK)

MAY 25 1951
SS CONSERVATION DIVISION
Wichita, Kansas

Eric H. Jager
Eric H. Jager

Subscribed to and sworn to before me, a Notary Public in said County and State this 23rd day of May, 1951.

Charlotte Keenan
Notary Public

My commission expires: 10-13-54

PLUGGING
FILE SEC 34 T 21 R 13 W
BOOK PAGE 83 LINE 40