

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 34 TWP. 21S RGE. 13 NE/W
Location as in quarters or footage from lines:
SE SE NE

Lease Owner Petroleum Energy, Inc.
Lease Name Hooper "B" Well No. 1
Office Address Suite 415 - 1st Natl. Bk. Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 12-1-83
Application for plugging filed 12-1-83
Plugging commenced 12-1-83
Plugging completed 12-1-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	303'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 40 sx cement @ 3680' thru drillpipe
Spotted 50 sx cement @ 790' thru drillpipe
Spotted 50 sx cement @ 340' thru drillpipe
Set bridge plug and spotted 40 sx cement @ 40' thru drillpipe.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita
(Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of Dec, 19 83


My Commission expires:  David F. Jamis
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1983

CONSERVATION DIVISION
Wichita, Kansas

12-28-83



15.185.21875.0000

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Petroleum Energy, Inc., Suite 415 - 1st Natl. Bk. Bldg., 105 N. Main,
 Wichita, Kansas 67202
 CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Hooper "B" Well No. 1
 Sec. 34 T. 21S R. 13W Spot SE SE NE
 County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 303' with 250 sx. 2% Gel 3% CC
 Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3690'

Drilling Commenced 11-22-83 Drilling Completed 12-1-83

Formation	From	To	Tops
Cellar	0	7	Anhydrite 720
Sand, Shale	7	303	Arbuckle 3687
Red Rock, Shale	303	720	
Shale, Lime	720	1640	
Shale, Sand	1640	2085	
Shale, Lime	2085	3375	
Lime	3375	3610	
Lime, Conglomerate	3610	3687	
Lime	3687	3690	

RECEIVED
 STATE CORPORATION COMMISSION

DEC 2 R 1983

CONSERVATION DIVISION
 Wichita, Kansas