

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kearney SEC. 4 TWP. 21S RGE. 35W E/W  
Location as in quarters or footage from lines:  
C of SE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner J. A. Allison  
Lease Name Van Doren B-1 Well No. \_\_\_\_\_  
Office Address 300 W. Douglas, Suite 305, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 5/20/81  
Plugging completed 5/28/81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4700  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	335	None
				5 1/2	4699	2369

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Moved in. Squeezed casing with 50 sacks cement. Pumped plug to 4200'. Pulled 20"  
tension. Made shots at 2425 and 2360 and pulled total of 77 joints. Squeezed hole with  
35 sacks cement, 10 sacks gel, 35 sacks cement and 15 sacks gel. Released plug, 50  
sacks cement and 5 sacks gel. Displaced with 10 sacks cement. Plugging complete.

RECEIVED

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING STATE CORPORATION COMMISSION

JUN - 4 1981


STATE OF Kansas COUNTY OF Rice, ss. CONSERVATION DIVISION  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June 19 81

Joan Kelso  
Notary Public.

My Commission expires:



DRILLER'S LOG

15.093.20727.0000

J. A. ALLISON  
Van Doren 'B' #1  
C SE SW  
Section 4 - 21S - 35W  
Kearny County, Kansas

Commenced: 3/17/81  
Completed: 3/26/81

Surface casing: 326' of 8-5/8"  
cmtd w/250 psi Class H, 3% cc,  
2% gal.

FORMATION

DEPTH

Surface hole	0 - 335
Shale	335 - 820
Shale & Sand	820 - 1700
Shale	1700 - 2935
Limo & Shale	2935 - 3145
Shale	3145 - 3490
Shale & Lime	3490 - 3790
Lime & Shale	3790 - 4355
Lime	4355 - 4700 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1981  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

CHEYENNE DRILLING, INC.

*A. J. Jacques*  
A. J. Jacques

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 31st day of March, 1981.

My Commission Expires: March 18, 1981

*Sharyn K. Shearnire*

Sharyn K. Shearnire, Notary Public

