

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-21,283.0000

LEASE NAME Klein 'B'

WELL NUMBER #1

4840 Ft. from S Section Line

440 Ft. from E Section Line

SEC. 4 TWP. 21 RGE. 35 (E) or (W)

COUNTY Kearny

Date Well Completed 8-27-93

Plugging Commenced 4-22-94

Plugging Completed 4-22-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. #1, Box 56 Great Bend, Ks. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Original 9-15-93 by David P. Williams (date)

by Extended date verbally by Steve Durrant 4-12-94 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Johnson/Cherokee Depth to Top 4611 Bottom 4827 T.D. 5046 KB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Johnson	Oil	4616	19	8 5/8	289	None
Cherokee	Oil	4719	21	4 1/2	4915	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 10 sacks 60/40 poz down 4 1/2 - 8 5/8 annulus PSI 500# - held.

Mix 300# hulls - 240 sacks 60/40 Poz 8% Gel, displace down 4 1/2 casing max pressure 800#.

Shut in with 800# standing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address Rt. #1, Box 56 Great Bend, Ks. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie (Employee of Operator A. L. Abercrombie, Inc.) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E. L. Abercrombie

(Address) Rt. #1, Box 56, Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 94

Susan M. Evers
Notary Public

My Commission Expires: 7-29-96