

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kearney SEC. 4 TWP. 21S RGE. 35W E/W
Location as in quarters or footage from lines:
C of SW SE

Locate Well
correctly on above
Section Platt.

Lease Owner J. A. Allison
Lease Name Van Doren #1 Well No. _____
Office Address Suite 305, 300 W. Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/19/81
Plugging completed 5/28/81
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation _____ Depth to top _____ bottom _____ T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	285	None
				5 1/2"	4694	2841'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Squeezed 5 1/2" casing with 50 sacks cement. Pumped plug to 4200. Pulled 23" tension. Gained to 28". Made shots at 3640, 3435, 3195, 2995 and 2825. Pulled total of 69 joints. Welder changed 8-5/8" collar. Squeezed hole with 35 sacks cement, 10 sacks gel, 35 sacks cement and 15 sacks gel. Released plug, 50 sacks cement and 5 sacks gel. Displaced with 10 sacks cement. Plugging complete.

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

JUN - 4 1981

6-4-81

STATE OF Kansas COUNTY OF Rice, ss.


CONSERVATION DIVISION
Wichita, Kansas

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1981

My Commission expires:



Joan Kelso
Notary Public.

DRILLERS LOG

VAN DOREN NO. 1

CASING RECORD:	OPERATOR: J. A. Allison	DESCRIPTION:
8-5/8" set @ 285' w/300 sax cement	CONTRACTOR: Sage Drilling Co.	C SW SE Sec. 4-21S-35W Kearny Co., Kansas
TOTAL DEPTH: 5050'	COMMENCED: December 21, 1975	ELEVATION: 3174KB
	COMPLETED: January 6, 1976	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	302	
Shale	302	825	
Shale & Sand	825	1426	
Shale	1426	2142	
Shale & Lime	2142	2251	
Anhydrite	2251	2275	
Shale & Lime	2275	2580	
Lime & Shale	2580	3120	
Shale & Lime	3120	3260	
Lime & Shale	3260	3590	
Shale & Lime	3590	3820	
Lime & Shale	3820	4200	
Shale & Lime	4200	4345	
Lime	4345	5050	


RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1981
CONSERVATION DIVISION
Wichita, Kansas

D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By *Tom M. Cault*



Subscribed and sworn to before me this 15th day of January, 1976.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1978.