

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-21237-0000

LEASE NAME Schmitz

WELL NUMBER 1-15

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 15 TWP. 21 RGE. 34 ~~NE~~ or (W)

COUNTY Finney

LEASE OPERATOR Mustang Oil & Gas Corporation

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202

PHONE#(316) 267-8011 OPERATORS LICENSE NO. 5652

Date Well Completed 10-05-93

Character of Well Oil

Plugging Commenced 06-01-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 06-01-94

The plugging proposal was approved on June 1, 1994 (date)

by Gene Barlow (District #1) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top 4705' Bottom 4716' T.D. 4840'
PBSD 4807'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	301'	None
				4-1/2"	4839'	2608'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Oil & Gas Corporation* License No. 5652

Address 100 S. Main, Suite 300, Wichita, KS 67202 *Service Co: Allied Cementing Co., Inc.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar, Exploitation & Production Mgr. (Employee of Operator) or Wayne L. Brinegar (widow of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Brinegar

(Address) 100 S. Main, Suite 300
Wichita, KS 67202



AND SWORN TO before me this 7th day of June, 19 94

Patricia A. Reilley
Notary Public

My Commission Expires: August 11, 1995

RU DS&W Well Service Co. Sumped 110 gals sand & set 5 sxs cement plug @4655'
Shot-off 4½" casing @2608' and pulled. RU Allied and spotted cementplugs as
follows:

50 sxs @2500' w/2 sxs gel spacer

80 sxs @1100' w/2 sxs gel spacer

30 sxs @600' w/2 sxs gel spacer

50 sxs @330' w/2 sxs gel spacer

20 sxs on top to fill to surface.

Total 235 sxs 60-40 Pozmix w/2% gel. Job completed @1:30 pm 6-1-94. Plugging
witnessed by KCC District #1 representative Gene Barlow.