

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS, 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20256-00-00

LEASE NAME Vaughn

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 15 TWP. 21 RGE. 34 (E or W)

COUNTY Finney

LEASE OPERATOR Nadel and Gussman, L.L.C.

ADDRESS 3200 First Place Tower Tulsa, OK 74103

PHONE (918) 583-3333 OPERATORS LICENSE NO. 32638

Date Well Completed 6-9-77

Character of Well GAS

Plugging Commenced 12-21-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-21-01

The plugging proposal was approved on 12-20-01 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation Council Grove Depth to Top 2849 Bottom 2649 T.D. 3080

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>501</u>	<u>-</u>
				<u>4 1/2</u>	<u>3014</u>	<u>1130</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Mixed 2 5x hulls to 20 5x cmt to plug perfs from 2849 to 2649. Recover 1130 4 1/2. Circ. hole w/mud to mixed 80 5x 1100 to 860, 50 5x 550 to 400 10 5x 40 to 0 Cut off & capped 8 3/4 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

RECEIVED
FEB - 4 2002

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: NADEL and Gussman KCC WICHITA

STATE OF Oklahoma COUNTY OF Tulsa, ss.

James Piland (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) James Piland

(Address) 3200 First Place Tower

Tulsa OK 74103

Notary Public Oklahoma
OFFICIAL SEAL

SUBSCRIBED AND SWORN TO before me this 31st day of January, 2002

Kathy Laverne
Notary Public

My Commission Expires: 8-1-03



SARGENT AND HORTON PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

№ 2380

DAILY REPORT

DATE 12-20-01 FROM 12⁰⁰ TO 6⁰⁰

COMPANY

FARM NO.

Nadel & Gussman, LLC. Vaughn 1-15

HOURS WORKED

NAME

6

D. Horton

6

J. Schoolcraft

6

A. Pineda

6

G. Sanborn

CONTRACTOR'S TIME _____ COMPANY'S TIME 6

REMARKS: Move on from S. of Garden City
Rig up pole. Backhoe dug cellar &
pit. Unpack casing head. Rig up
jacks & measured stretch. Showed
stuck @ 850. Rig up pump truck.

SARGENT AND HORTON PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

№ 2381

DAILY REPORT

DATE 12-21-01 FROM 7⁰⁰ TO 5⁰⁰

COMPANY

FARM NO.

Nadel & Gussman Vaughn 1-15

HOURS WORKED

NAME

10

D.H.

10

J.S.

10

A.P.

10

G.S.

CONTRACTOR'S TIME

4

COMPANY'S TIME

1/2

REMARKS: Mixed 2 5x hulls to 20 5x cont.
to plug perfs from 2849 to 2649.
Shot 4 1/2 @ 1130 where it worked
loose. Pulled to 1100. Circ. hole w/mud &
mixed 80 5x plug from 1100 to 860. Pull
to 550. Mixed 50 5x plug from 550 to
400. Pull to 40. Mixed 10 5x 40 to 0. Ld
out jacks. Tore down pole & pump truck.

SARGENT AND HORTON PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

NO 2382

DAILY REPORT

DATE 12-27-01 FROM 7⁰⁰ TO 11⁰⁰

COMPANY

FARM NO.

Nadel and Gussman Vaughn 1-15

HOURS WORKED

NAME

4

D.H.

4

J.S.

4

A.P.

4

G.S.

CONTRACTOR'S TIME _____ COMPANY'S TIME 4

REMARKS: Clean out cellar. Cut off & cap-
ped 8⁵/₈ 3 ft. below G.L. Tally pipe.