

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202
 KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-093-20154-00-00

LEASE NAME ODD Williams

WELL NUMBER 1-12

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 12 TWP. 21S RGE. 35W (~~35E~~ (W))

COUNTY Kearney

Date Well Completed 4/75

Plugging Commenced 4/12/93

Plugging Completed 4/13/93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

JUN 02 1993

CONSERVATION DIVISION

LEASE OPERATOR KCS Coastal Oil & Gas Corporation

ADDRESS P. O. Box 749 Denver, CO 80201-0749

PHONE# (303) 573-4476 OPERATORS LICENSE NO. 6593

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/9/93 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow/Drum/Lansing Depth to Top 4090' Bottom 4859' T.D. 5060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	0	601	8-5/8	601	0'
Drum LS	100% SW	0	4958	4-1/2	4958	0'
Lansing	100% SW					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate hole w/9.0 ppg mud. Spot balanced cmt plug from 4848'-4700' w/15 sx. Spot balanced cmt plug from 4197'-3940' w/25 sx. Perforate 1198'-1200', 4 JSPF and pump 175 sx down 4-1/2". Pumped 125 sx down 8-5/8" x 4-1/2" annulus. Cut casing 4' BGL and weld on metal plate. Restored location. Job witnessed by Steve Middleton - KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Coastal Oil & Gas Corp./Halliburton License No. 5287 Howco

Address P. O. Box 749 Denver, CO 80201-0749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coastal Oil & Gas Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Eileen Danni Dey (Employee of Operator) ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Eileen Danni Dey

(Address) P. O. Box 749 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 93

Tareen Hurst
 Notary Public

My Commission Expires: June 7, 1995