

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,311-0000

LEASE NAME Ronald Ross

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 21 TWP. 28 RGE. 17 (E or W)

COUNTY Kiowa County

LEASE OPERATOR Advantage Resource - Schuelin Company

ADDRESS 1755 Sherman Street, Denver, Colorado 80203

PHONE# (303) 831-1912 OPERATORS LICENSE NO. Advantage 6926 Date Well Completed 5-2-91

Schuelin 6785

Character of Well Dry hole

Plugging Commenced 9:00 PM

5-2-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-2-91-10:30PM

The plugging proposal was approved on May 2, 1991 (Date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? X

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
5-10-91
MAY 10 1991
CONSERVATION DIVISION
Wichita, Kansas

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	397'KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Filled hole with heavy mud. 50 sacks at 1140', 80 sacks at 575', 50 sacks at 400'
10 sacks 40' to surface, 15 sacks in rathole, 10 sacks in mousehole,
used 60/40 Pozmix W/ 6% gel. By Allied Cementing Company
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling

STATE OF Kansas COUNTY OF Kiowa, ss.

Richard L. Mead, Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, Agent

(Address) PO Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 3 day of May, 19 91

Agnes D. Wurst
Notary Public Agnes D. Wurst

My Commission Expires: 4-26-93



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG -----RONALD ROSS #1
 C NE NE, Sec. 21-T28S-R17W, Kiowa County, Kansas

OPERATOR: Advantage Resources Inc.
 Schuelin Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 25, 1991

COMPLETED: May 2, 1991

TOTAL DEPTH 4875' Driller TD
 4871' Log TD

- LOG -

0 - 150' Surface soil & sand
 150 - 400' Shale & Sand
 400 - 1116' Lime & Shale
 1116 - 4875' Lime & Shale

CASING RECORD

Spud at 10:30 AM 4-25-91 Drilled 400' of
 12 1/4" hole. Ran 9 joints new 8 5/8"
 20# casing. 384.98' pipe set at 397' KB.
 Cemented with 200 sacks 60/40 Pozmix, W/
 2% gel, 3% cc. Plug down at 4:30 PM 4-25-91
 by Allied Cementing. Good returns to surface.

Plugged as follows:

Filled hole with heavy mud W/ 50 sacks at
 1140', 80 sacks at 575', 50 sacks at 400',
 10 sacks 40' to surface, 15 sacks in rathole.
 10 sacks in mousehole. Used 215 sacks 60/40 Pozmix
 W/ 6% gel. Job complete at 10:30 PM May 2,
 1991 By Allied Cementing. State Plugger - Steve
 Middleton W/ KCC was not present. Tom Myers
 was Sterling Drilling witness

DEVIATION SURVEYS:

4825' - 1/4°

RECEIVED
 STATE CORPORATION COMMISSION

MAY 10 1991

CONSERVATION DIVISION
 Wichita, Kansas