

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 1979

KANSAS

Form CP-3  
Rev. 6-4-68

CONSERVATION DIVISION  
Wichita, Kansas

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -185-19559.0000 (of this well)

Operator's Full Name Bergman Oil Co.

Complete Address 520 union Center, Wichita, Ks. 67202

Lease Name Fisher Well No. 1

Location NW NE SW Sec. 17 Twp. 21s Rge. 13 (E)  (W)

County Stafford Total Depth 3681

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N Day 21 Month 3 Year 1979

The above well was plugged as follows:

320' 8 5/8" casing w/ 250 sax cement. 5 1/2" casing set @3675' w/ 150  
sax cement. Open hole. Sand back to 3650'-Top sand w/ 5 sax mixed  
cement w/ dump bailer. Pull 2705' 5 1/2" casing. Allied mixed & -  
pumped 5 sax hulls-25 sax gel, 100sax 50/50 posmix cement w/4% gel &  
4% CC to top of casing. Shut in w/300# pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3-28-79

INV. NO. 9334-W