

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address Rt #2 Great Bend, Ks 67530

Lease Name Fischer Well No. E-1

Location NE/SW/NW Sec. 17 Twp. 21 Rge. 13 (E) (w)X

County Stafford Total Depth 3663

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 11:00AM Day 12 Month 2 Year 1970

The above well was plugged as follows:

290 ft of 8 5/8 surface pipe circulated with 225 sacks cement.
3659 ft of 5 1/2 long string cemented with 125 sacks. Top Perf 3468 ft.
Sand back to 3450 ft, 5 sacks cement with bailer. Set overnight
bridge at 280 ft, 6 sacks cement with bailer. 10 ft rock bridge,
25 sacks cement, mud to 40 ft, 10 ft rock bridge, 10 sacks cement.
to top of surface. 3000 ft of 5 1/2 pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed J. Russell M. Kersting
Well Plugging Supervisor

DATE 2/16/70
INV. NO. 1423-W