

R

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Fred Schaffer

Complete Address: 404 Walcott Bldg., Hutchinson, Kansas

Lease Name Fischer Well No. # 1

Location App. NW SE NW Sec. 17 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3685'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Bert Self Casing Pulling Company

Address: Route 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 12:30 PM Day 23rd Month May Year 1966

The Above well was plugged as follows:

332' of 8 5/8" surface pipe, cement circulated. 3681' of 5 1/2" long string,
cemented to 2850'. Top perforation 3671'. Bottom of the hole was sanded to
3600', and cemented with 5 sacks. 1900' of 5 1/2" long string was recovered from
the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to
315'. 6 sacks of cement was mixed in a barrel, and put on plug at 315', through
the dump bailer, and let set for 2 days. Hole was bailed dry, and 20 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 5-26-66

INV. NO. 3283-W