

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 81-20

LOCATION SW-SW-SW

SEC. 19 TWP. 21 RGE. 16-W¹⁵

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Torrance

Operator J. M. Huber, Corp Address Box #460 - Pratt, Kansas

Field _____ County Pawnee

Total Depth 3867 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 950 ft. Circulated with cement.
5/8 casing set at 3775 - Filled back from bottom to
3775 ft with chat - Shot off & Pulled 5/8 casing
dumped 5 sacks of cement at 3775 ft - Filled with mud
to 400 ft - Rock Bridge & 15 sacks of cement at 400 ft -
Mud to 30 ft - Plug & 10 sacks cement at the surface.
Frank Carroll - Plugging - Contractor

C. M. Stough
District Conservation Agent

Date 2 - RECEIVED

Conservation Div.

FEB 21 1949

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 19 T 21 R 16W
BOOK PAGE 81 LINE 20