

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Morgenstern Oil Operations

Complete Address: Box 372 Wichita, Kansas 67202

Lease Name Phinney Well No. 1

Location SW SW NE Sec. 36 Twp. 21 Rge. 15 (E) (W) XX

County Pawnee Total Depth 3860

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11.30A Day 24 Month 12 Year 1968

The Above well was plugged as follows:

Total Depth 3860' 8 5/8 csg set at 284' cwc 200 sk.

5 1/2 csg set at 3670' CW 100 sc cmt.

Set wood plug at 3600' poured 10' sand and dumped 5 sk cmt. with dump bailer.

Cutoff and recov. 2956' of 5 1/2 csg.

On 12-23-64 Pumped thru 8 5/8 swage with 20 sk gel W/4 sk hulls, plug and 100 sc cement.

On 12-24-68 ran wire line to top of cement. (90') Filled with 1 1/2 yd readymix cement. (0-90)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 12-26-68

INV. NO. 9096-W