

10-23-87 15.185.20131.0000

1 061027

API NUMBER 15-Drill completion 10/1/68

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SE, SEC. 20, T 21 S, R 12 W/R

2310 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Tieperman Well # 2-A

Operator: Lasmo Energy Corporation  
Name & Address: P.O. Box 1365  
Great Bend, KS 67530

County Stafford 113.43

Well Total Depth 3490 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 23 Month: 10 Year: 1987

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3491' Perfs at 3338-3464'

1st plug sand back to 3285' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 23 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3285' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 29 1987

Maximum pressure 600 psi and shut in 300 psi.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1758' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (observe this plugging.)

Signed Paul A. Luthi (TECHNICIAN)

DATE 11-3-87

INV. NO. 18728