

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30438-00-00
Spot: SWSESW Sec/Twnshp/Rge: 20-21S-12W
330 feet from S Section Line, 3650 feet from E Section Line
Lease/Unit Name: LUCY WALTER Well Number: 1
County: STAFFORD Total Vertical Depth: 3680 feet

Operator License No.: 9163
Op Name: JANDIE OIL CO., INC.
Address: PO BOX 442
GREAT BEND, KS 67530

Conductor Pipe: Size _____ feet: \$119.60
Surface Casing: Size 8.625 feet: 273
Production: Size 5.5 feet: 3677 WITH 175 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2001 1:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: FREDDIE D. WALLS Company: JANDIE OIL Phone: (316) 793-7288

Proposed Plugging Method: PER KCC REGULATIONS

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/24/2001 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3580-3618'. COMPANY ATTEMPTED CLEAN OUT WELL TO PUT IT BACK ON PRODUCTION. AFTER 2 DAYS THEY ONLY REACHED 680' AND WERE OUTSIDE OF 5 1/2" CASING. RAN OPEN END TUBING TO 680'. PUMPED 300 SX CMT. HAD GOOD CIRCULATION UP 5 1/2" CASING AND 8 5/8" X 5 1/2" ANNULUS. DID NOT GET CMT TO SURFACE. SDON SINCE IT WOULD BE 3 HOURS FOR MORE CMT TO REACH LOCATION. ON 01/24/01 TAGGED CMT AT 375'. PULLED TUBING TO 370' & PUMPED 225 SX CMT CIRCULATING CMT TO SURFACE UP BOTH 5 1/2" CASING AND 8 5/8" X 5 1/2" ANNULUS. PULLED TUBING TOPPED OFF HOLE WITH 15 SX CMT.

INVOICED
DATE 03-07-2001
INV. NO. 2001061412

RECEIVED
STATE CORPORATION COMMISSION
1-31-01
JAN 31 2001

Remarks: USED 60/40 POMIX 2% GEL BY COPELAND ACID & CEMENT. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

JAN 26 2001

Handwritten initials

Handwritten initials