

To: 1 052094  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drilled 12/49 15.185.13083.0000  
N/2 N/2 NW, SEC. 20, T 21 S, R 12 W/E  
4950 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6568  
Operator: Kaiser-Francis Oil Company  
Name & Address  
P.O. Box 21468  
Tulsa, OK 74121-1468

Lease Name Hall Well # 2  
County Stafford  
Well Total Depth 3550 115.37 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug-at: Hour: 7:30 a.m. Day: 9 Month: 12 Year: 19 96  
Plugging proposal received from Manny Boatright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 3524' w/150 sx cement, PBSD 3541', Open hole 3524-41'  
1st plug sand back to 50' above open hole and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

DATE 12-16-96

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 8:45 a.m. Day: 9 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3475' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, and 125 sx cement.  
Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (did not observe) this plugging.

**INVOICED**  
DATE JAN 03 1997  
INV. NO. 47224

Signed Richard W. Lacey  
(TECHNICIAN)