

15.185.12465.0000

To: 1 120092
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-2879
NW SW SW, SEC. 20, T 21 S, R 12 W/EX
990 feet from S section line
4950 feet from E section line
Lease Name Lucy Walters Well # 2
County Stafford
Well Total Depth 4100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 200

TECHNICIAN'S PLUGGING REPORT
Operator License # 5692
Operator: Fina Oil & Chemical Company
Name & Address: Box 209
Russell, KS 67665

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor: Fina Oil & Chemical Company License Number 5692
Address: Box 209, Russell, KS 67665

Company to plug at: Hour: 9 a.m. Day: 28 Month: 1 Year: 19 88

Plugging proposal received from Don Tiffin
(company name) Fina Oil & Chemical Company (phone) 913-483-2102

were: 5 1/2" at 3750' 3 1/2" liner from 3740-3995' Cut window at 3684-94'. Deepened hole to 4100' in 1960. Ran 3 1/2" fiberglass tubing to 3575' in 1968.

1st plug run 1 1/2" tubing inside of 3" fiberglass tubing to TD and plug with cement from TD.

Plugging Proposal Received by: Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 15 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT Unable to get 1 1/2" tubing past 1140' inside the fiberglass.

The enclosed attachment explains what work was done and materials used in plugging the well. Total cement - 1815 sx various blends from common to ATL, mixed and pumped liquid diverter, diesel, bentonite, hulls, cello flake, wheat and salt mud. Cemented by Allied. No casing recovery.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.
STATE CORPORATION COMMISSION

Signed Duane Rankin
(TECHNICIAN)

APR - 7 1988
CONSERVATION DIVISION
Wichita Kansas

FORM CP-2/3
Rev. 01-84