

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21477-00-00
Spot: CNE Sec/Twnshp/Rge: 30-28S-17W
3840 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: CULLINS Well Number: 2-30
County: KIOWA Total Vertical Depth: 4904 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 159.38
Surface Casing: Size 8.625 feet: 533 WITH 150 SX CMT
Production: Size 4.5 feet: 4904 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/22/2003 9:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BACK TO 4790' WITH 4 SX CMT ON TOP. PLUG AT 1100' WITH 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/22/2003 10:30 AM KCC Agent: STEVE PFEIFER


Actual Plugging Report:

PERFS AT 4842-46 & 4852-58'. SANDED BACK TO 4780' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2". 1ST PLUG AT 1100' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3038' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
RECEIVED (TECHNICIAN)
FEB 13 2003
INVOICED Form CP 2A
KCC WICHITA DATE 2-14-03
INV. NO. 2003061203