

To: 1 090485.
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-12 API NUMBER 15- 097-21,380 - 0000
150' E of
NE NW NE, SEC. 31, T 28 S, R 17 W/E
330 feet from NXX section line
1500 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6926
Operator: Advantage Resources, Inc.
Name & Address 1775 Sherman St., Ste. 1375
Denver, CO 80203

Lease Name Dale E. West Well # 1
County Kiowa
Well Total Depth 5000 162.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 498

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 11:45 a.m. Day: 12 Month: 10 Year: 1994

Plugging proposal received from Joe
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

were: to fill hole with heavv mud and spot cement through drill pipe Anhydrite 1175'
1st plug at 1175' with 50 sx cement, 2nd plug at 520' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 p.m. Day: 12 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1175' with 50 sx cement,
2nd plug at 520' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

10-18-94

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1994

WICHITA CONSERVATION DIVISION
KANSAS

INVOICED

DATE 10-20-94

INV. NO. 41476

10-12 DEC 12 1994

Signed [Signature]
(TECHNICIAN)

EFFECTIVE DATE: 10-2-94

State of Kansas

097-21,380

FORM MUST BE TYPE

DISTRICT # 9

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

SEAL Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 29, 1994

Spot 150' E of NE - NW - NE Sec 31 Twp 28 S. Rg 17W

OPERATOR: License # 6926 Name: ADVANTAGE RESOURCES, INC. Address: 1775 Sherman Street, Suite 1375 City/State/Zip: Denver, Colorado 80203 Contact Person: Lou Bartz Phone: 303/831-1912

330 feet from SOUTH / North line of Section 1500 feet from East / West line of Section IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License # 5929 Name: DUKE DRILLING CO., INC.

(NOTE: Locate well on the Section Plat on Reverse Side; County: Kiowa Lease Name: Dale E. West Well #: 1 Field Name:

Well Drilled For: Well Class: Type Equipment:

- X. Oil ... Enh Rec .X Infield .X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... GVOO ... Disposal ... Wildcat ... Cable ... Seismic: ... # of Holes ... Other

Is this a Predrilled/Spaced Field? ... yes X no Target Formation(s): Lansing, Mississippi Nearest lease or unit boundary: 330'

If GVOO, old well information as follows:

Ground Surface Elevation: 2200 feet MSL Water well within one-quarter mile: ... yes X no

Public water supply well within one mile: ... yes X no

Depth to bottom of fresh water: 210'

Depth to bottom of usable water: 380'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 480'

Length of Conductor pipe required: N/A

Projected Total Depth: 5000

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

... well ... farm pond X other

DWR Permit #:

Will Cares Be Taken?: ... yes X no

If yes, proposed zone:

420' Alt. I Req.

Directional, Deviated or Horizontal wellbore? ... yes X no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 3/27/95

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual placement of this well

Pusher Joe SPUD DATE 10-3-94 INIT. SM LENGTH SURFACE PLANNED 480 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2" @ 998 CONDUCTOR ANHYDRITE T- B-1175 ELEVATION TD 5000' FORMATION MISS RAN PIPE @ DV TOOL ALT II DONE SX Y N SX Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 175 Ft. W/ 50 SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 520 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 12 SX MOUSE HOLE W/ 12 SX WATER WELL P. V. W. SX (Irr. Well Pond Hauling) TECHNICIAN SAA DATE 10-11-94 TYPE OF CEMENT 60/40/60 DATE 10-12-94 STARTING TIME 8:45 AM/PM DATE 10-12-94 COMPLETION TIME 1:15 AM/PM DATE 10-12-94 CEMENT COMPANY Calced.