

1 080462

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,184 . 00.00
150 E of C SW, SEC. 28, T 30 S, R 17 W
1320 feet from S section line
3810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Elwell "A" Well # 1
County Kiowa 166.08
Well Total Depth 5110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 397

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 West Fowler, Medicine Lodge, KS67104

Company to plug at: Hour: 10:45 am Day: 27 Month: December Year: 1985

Plugging proposal received from Elmo Morgenstern
(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5095' PBTD 5070' Perfs at 4974-80'; 4986-92'; 4996-5002'

1st plug sand back to 4925' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 10 3/4" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 27 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4925' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 400 psi

Remarks: Recovered 3646' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 06 1986
INV. NO. 11853

JAN 2 1986

Signed J. A. [Signature] (TECHNICIAN)