

1 080508

API NUMBER 15- 097-21,081 . 00.00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW NE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SEC. 28 T30 S, R 17 (W/E)

4040 feet from S section line

3900 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Booth "C" Well # 1

Operator: TXO Production Corp.

County Kiowa 161.92

Name & Address 155 N. Market, Suite 1000

Well Total Depth 4982 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor TXO Production Corp. License Number 5171

Address 155 North Market, Suite 1000, Wichita, KS67202

Company to plug at: Hour: 2:45 pm Day: 25 Month: March Year: 1986

Plugging proposal received from Rex Cravens

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4981' PBD 4979' Perfs at 4791-96'

1st plug down 4 1/2" pump 1 sack hulls, 20 sx cement, 23 sx gel, and 70 sx cement

2nd plug pump 125 sx cement down annulus

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:30 pm Day: 25 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls, 20 sx cement, 24 sx gel, 70 sx

cement Maximum pressure 1000 psi and shut in 700 psi

2nd plug pumped 125 sx cement down backside. Maximum pressure 250 psi and shut in 75 psi

APR 7 1986

Remarks: No recovery. Used 60/40 Pozmix 6% gel by BI-Titan. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If possible) observe this plugging.

Signed J. A. [Signature] (TECHNICIAN)

DATE APR 7 1986

INV. NO. 13321  
3-25

MAY 08 1986