

6-2-88 15.185.27408.0000

1 040112

API NUMBER 15-Drill Completion Date 5/10/61

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NW, SEC. 36, T 21 S, R 12 W/EX

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6939

Lease Name Mellies "A" Well # 2

Operator: Chapman Exploration, Inc.

County Stafford 115.70

Name & Address 6100 South Yale, Suite 1816

Well Total Depth 3560 feet

Tulsa, OK 74136

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 2 Month: 6 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3557' Perfs at 3286-90, 3540-60; Open hole at 3557-60'

1st plug sand back to 3235' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hull, wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN - 7 1988

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 2 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3235' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8.5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

6-29-88

DATE

INV. NO. 21104

Signed Stephen J. Pfeifer
(TECHNICIAN)