

8-21

15.185.01187.0001

To: 1 070018
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Docket #E-12,920
SE SE NE, SEC. 36, T 21 S, R 12 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

Lease Name Mellies Well # 2
County Stafford 117.94
Well Total Depth 3629 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Service License Number 6901
Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 8 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Service (phone) 316-587-3361

work: 5 1/2" at 3629' w/150 sx cement, Perfs at 3504-08', Tubing cemented in from 3400-1400±'

1st plug pump 25 sx cement down tubing, displace to 1500',

2nd plug circulate cement to surface down 5 1/2" casing,

3rd plug pump 170 sx cement down 8 5/8".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:50 a.m. Day: 21 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug on 8/6/97-pumped 25 sx cement down tubing to 1500' with 1250 psi-witnessed by Richard Lacey.

2nd plug circulated cement to surface with 81 sx, through 5 1/2 casing

3rd plug pulled 5 1/2" casing and pumped 170 sx cement down 8 5/8". Maximum pressure 600 psi and shut in 350 psi.

8-29-97

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 346' of 5 1/2 casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (BY) / (XXXXXX) observe this plugging.

DATE 9-4-97

Signed [Signature] (TECHNICIAN)

INV. NO. 48891