

1 120802

6-25

15.195.20684.0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-25,256
NW SW SW
SEC. 36 T 21 S, R 12 W/4
1245 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Mellies Well # A #5

Operator: Globe Exploration, Inc.

County Stafford

Name & Address P.O. Box 12

Well Total Depth 3520 114.40 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 25 Month: 6 Year: 19 93

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3515' w/100 sx cement, PBSD 3496', Perfs at 3292-96, 3431-33, 3450-54'
1st plug sand back to 3240' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:10 p.m. Day: 25 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3240' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2040' of 5 1/2" casing.

RECEIVED STATE CORPORATION COMMISSION

JUN 29 1993

CONSERVATION DIVISION Wichita, Kansas

INVOICED

I (did observe this plugging.

DATE: JUL 13 1993

Signed Duane Rankin (TECHNICIAN)

INV. NO. 38089