

To: 1 120803 15.185.22450.0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
206 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-25 185-22,450
API NUMBER 15-
NW SW SW
SEC. 36 T 21 S, R 12 W/SE
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name Sittner Well # 7

Operator: Globe Exploration, Inc.
Name & Address: P.O. Box 12
Great Bend, KS 67530

County Stafford
Well Total Depth 3659 118.91 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address: P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 25 Month: 6 Year: 19 93

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3659' w/150 sx cement, Perfs at 3502-08, 3407-09, 3368-71'

1st plug sand back to 3318' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 25 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3315' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 800 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2453' of 5 1/2" casing. If additional description is necessary, use BACK of this form.

INVOICED
DATE 7-13-93
BY 38088

Signed Duane Rankin (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1993
CONSERVATION DIVISION
Wichita, Kansas