

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21807-00-00  
Spot: CN2N2NE Sec/Twnshp/Rge: 36-21S-12W  
330 feet from N Section Line, 1320 feet from E Section Line  
Lease/Unit Name: MELLIES Well Number: 4  
County: STAFFORD Total Vertical Depth: 3572 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

Conductor Pipe: Size feet: #116.09  
Surface Casing: Size 8.625 feet: 261 WITH 225 SX CMT  
Production: Size 4.5 feet: 3562 WITH 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/30/2003 8:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3420' & 4 SX CMT. PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/30/2003 10:50 AM

KCC Agent: RICHARD LACEY


Actual Plugging Report:

OPEN HOLE AT 3562-3572'. SANDED BOTTOM TO 3470' & 4 SX CMT WITH DUMP BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 150#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1210' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

FEB 04 2003

KCC WICHITA

INVOICED

DATE 2-5-03

INV. NO. 2003061163