

1 080218

15.185.01480.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available
SE C SE , SEC. 29, T 21 S, R 12 W/E
1320 feet N SE Corner of ~~XXX~~ section line
660 feet W SE Corner of ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5354

Lease Name Mueller I Well # 1
County Stafford 117.20

Operator: Southern States Oil Co.
Name & Address Box 1365
Great Bend, KS 67530

Well Total Depth 3606' feet
Conductor Pipe: Size feet
Surface Casing: Size 12' feet 248

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 17 Month: September Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5" at 3596' PBD 3598'

1st plug sand back to 3170' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 150 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 am Day: 17 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5" at 3596' PBD 3598'

1st plug sanded back to 3170' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 150 sx cement.

STATE CORPORATION COMMISSION

OCT 01 1984

Maximum pressure 400 psi and shut in pressure 100 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 400' of 5 1/2" casing. Used 60/40 Pozmix 2% gel 3%cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed J. H. Metz (TECHNICIAN) SD

DATE 10-3-84

INV. NO. 4068