

1 061028

10-23-87 15.185.12630.0000

API NUMBER 15-Drill completion 6/23/47

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C N/2 NW SE, SEC. 29, T 21 S, R 12 W/R  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2310 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Mueller A Well # 3

Operator: Lasmo Energy Corporation

County Stafford 116.29

Name & Address P.O. Box 1365

Well Total Depth 3578 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:15 a.m. Day: 23 Month: 10 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3577' PBSD 3450' Perfs at 3299-3426'

1st plug sand back to 3250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 a.m. Day: 23 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 29 1987

Maximum pressure 550 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1560' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

Signed Paul A. Luthi (TECHNICIAN)

DATE 11-3-87

INV. NO. 18730