

To: 1 052111 m 2-26 API NUMBER 15-Spud date 1/15/46

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION N/2 NW NW, SEC. 29, T 21 S, R 12 ~~WXXX~~

130 S. Market, Room 2078 15195-01631-0000
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT
330 feet from N ~~S~~ section line
660 feet from W ~~E~~ section line

Operator License # 4967 Lease Name Fischer A Well # 5

Operator: Berenergy Corporation County Stafford 117.19

Name & Address P.O. Box 5850 Well Total Depth 3606 feet

Denver, CO 80217 Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 306.35

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 26 Month: 2 Year: 19 97

Plugging proposal received from Bruce Patterson

(company name) Berenergy Corp. (phone) 303-295-2323

were: 5 1/2" at 3595' w/100 sx cement, 4 1/2" slotted liner 3568-3606', Perfs at 3398-3416'
Squeezed at 500' and 300' to surface.

1st plug set CIBP at 3000' with 2 sx cement on top,

2nd plug at 1500' with 25 sx cement through tubing,

3rd plug at 800' to surface, circulate.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 26 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3005' with 2 sx cement on top,

2nd plug ran tubing to 1500' and pumped 25 sx cement, 3rd plug pulled tubing to 800' and pumped

30 sx cement, 4th plug pulled tubing to 500' and pumped 30 sx cement, 5th plug pulled tubing to

200' and pumped 30 sx cement, 6th plug pulled tubing out and topped off hole.

Good circulation throughout job.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE MAR 11 1997 Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 47719

2-26 FORM CP-2/3
Rev. 01-84

RECEIVED
KANSAS
STATE
CORPORATION
COMMISSION
MAR 10 P 3:19