

To: 1 040773 8-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15.185-12632-0000 Drill completion date 6/27/44
S/2 SE SW, SEC. 29, T 21 S, R 12 W/EX
330 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Teiperman A Well # 2

Operator: Energy Three, Inc.

County Stafford

Name & Address P.O. Box 1505

Well Total Depth 3607 117.22 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 10 Month: 8 Year: 19 93

Plugging proposal received from Dallas Folds

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3597' w/125 sx cement, Open hole 3597-3607'

1st plug sand back to 3547' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 10 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3547' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1716' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

AUG 18 1993

INVOICED
(did / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE 8-24-93

Signed Stephen J. Teiper
(TECHNICIAN)

REV. NO. 38399