

8-23-88

15.195.12587.0000

1 120129

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 3/23/45

S/2 NW SW, SEC. 29, T 21 S, R 12 W/E

1650 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Tieperman A Well # 4

Operator: LASMO Energy Corporation

County Stafford 116.51

Name & Address P.O. Box 1365

Well Total Depth 3585 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor LASMO Energy Corporation License Number 4678

Address P.O. Box 1365, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 23 Month: 8 Year: 19 88

Plugging proposal received from Rodger Reddick

(company name) LASMO Energy Corporation (phone) 316-792-2585

were: 5 1/2" at 3583' PBT 2100' Perfs at 3345-3476' (5 sets) Elevation 1863'

1st plug pump down 5 1/2" with 3 sx hulls and 30 sx cement, put in gel spacer to Anhydrite,

2nd plug fill with cement from Anhydrite to surface.

3rd plug fill backside with cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 23 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" with 250 lbs. hulls, 20 sx cement,

23 sx gel, 50 lbs. hulls, and 130 sx cement.

Pumping pressure 0-900 psi and shut in 900 psi.

Casing squeezed at 2700' and 288' with 150 sx cement each.

Remarks: Used 60/40 Pozmix 6% gel by Howco. No casing recovery.
(Additional description is necessary, use BACK of this form.)

(old / ~~XXXXXX~~) observe this plugging.

DATE 8-31-88

Signed [Signature]
(TECHNICIAN)

INV. NO. 22061

RECEIVED
CORPORATION COMMISSION
AUG 30 1988
CONSERVATION DIVISION
WICHITA, KANSAS