

R

To: 1 030975
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 8/26/45

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

_____ feet from S section line
_____ feet from E section line

Operator: LASMO Energy Corporation
Name & Address: P.O. Box 1365
Great Bend, KS 67530

Loose Name Tieperman A Well # 5
County Stafford 116.77
Well Total Depth 3593 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION
SEP - 8 1988
CONSERVATION DIVISION
Wichita, Kansas

Company to plug at: Hour: 4 p.m. Day: _____ Month: 8 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3591' Open hole Elevation 1862'
1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:50 p.m. Day: 31 Month: 8 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1825' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(Add appropriate) observe this plugging.

DATE 9-9-88

Signed Steve Pfeifer (TECHNICIAN)

INV. NO. 22200
8-31