

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12584-00-00
Spot: CS2SENE Sec/Twnshp/Rge: 29-21S-12W
3300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: TEIPERMANN B Well Number: 1
County: STAFFORD Total Vertical Depth: 3583 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1430 LELIA DRIVE STE 200
JACKSON, MS 39216

Conductor Pipe: Size _____ feet: 3 1/6.45
Surface Casing: Size 8.625 feet: 300 WITH 210 SX CMT
Production: Size 5.5 feet: 3581 WITH 125 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2002 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PLOUGHOF Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 3340' & 5 SX CMT WITH DUMP BAILER. PLUG AT 650' WITH 10 SX GEL - 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/16/2002 3:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3581.5'. PERFS AT 3468-76, 3445-50, 3427-31, 3401-12, 3394-98'. SANDED TO 3340' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 650' WITH 10 SX GEL - 50 SX CMT. NO CIRCULATION. 2ND PLUG AT 330' WITH 21 SX GEL & 500# HULLS GOT CIRCULATION. PUMPED 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
OCT 22 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED OCT 18 2002

DATE 10-22-02

INV. NO. 2003060694

Form SP-2/3