

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12585-00-00
Spot: CS2SWNE Sec/Twnshp/Rge: 29-21S-12W
2970 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: TIEPERMANN B Well Number: 2
County: STAFFORD Total Vertical Depth: 3584 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1430 LELIA DRIVE STE 200
JACKSON, MS 39216

Conductor Pipe: Size feet: 3 1/2" 48
Surface Casing: Size 8.625 feet: 282 WITH 210 SX CMT
Production: Size 5.5 feet: 3582 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/18/2002 3:15 PM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 3250' & 5 SX CMT. PLUG AT 650' WITH HULLS & 50 SX CMT. PLUG AT 310' WITH HULLS & 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/18/2002 4:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3584'. OPEN HOLE 3582-3584'. 5 1/2" CASING FULL OF HOLES. WAIT ON 2 3/8" TUBING TO PLUG THROUGH. SANDED BACK TO 3250' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 650' WITH 300# HULLSMIXED IN WITH 10 SX GEL & 100# HULLS MIXED IN WITH 50 SX CMT. 2ND PLUG AT 310' WITH 100# HULLS MIXED IN WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
OCT 24 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1680' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED OCT 21 2002

DATE

10-24-02

INV. NO.

2003060703

FORM CP-2/3