

To: 1 052189 // - //  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-21,785  
150' W of  
NE SE SW, SEC. 17, T 21 S, R 13 W  
990 feet from S section line  
3120 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / \_\_\_\_\_

Lease Name Culbreath Well # 1

Operator: Kansas Corporation Commission

County Stafford

Name & \_\_\_\_\_

Well Total Depth 3711 feet

Address \_\_\_\_\_

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 11 a.m. Day: 11 Month: 11 Year: 19 97

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-338-1610

were: 5 1/2" at 3710' w/125 sx cement, Perfs at 3678-81'

Sand off bottom to 3600'. Pull all free 5 1/2" casing. Pump down 8 5/8" with 300 lbs. hulls,

10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125

sx cement.

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 11 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT Bridge at 1855'--could not get through it.

Spotted plugs through casing:

1st plug at 1500' with 2 sx gel, 50 sx cement, and 8 sx gel,

2nd plug at 750' with 50 sx cement with 100 lbs. hulls,

3rd plug at 400' with 50 sx cement,

4th plug at 40' with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)