

1 030943

5-5-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,513 .0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Operator: General Oil Company, Inc.  
Name & Address: 1540 North Broadway, Suite 202  
Wichita, KS 67214

150' S SE NE SE SEC. 17, T 21 S, R 13 W/E

1500 feet from S section line

330 feet from E section line

Lease Name Reiser Well # 1

County Stafford 121.19

Well Total Depth 3729 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman-Tannitti Drilling Company License Number 5122

Address Box 308, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 5 Month: 5 Year: 19 88

Plugging proposal received from Rich Wheeler

(company name) Woodman-Tannitti Drilling Company (phone) 316-792-1922

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 809'

1st plug at 810' with 50 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:45 a.m. Day: 5 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

Water well plugged with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 06 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If not observe this plugging.)

DATE 5-17-88

Signed Steve Krumm (TECHNICIAN)

INV. NO. 20637

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... April 26, 1988

API Number 15-185-22,513.0000

OPERATOR: License # 9069
Name: General Oil Company, Inc.
Address: 1540 N. Broadway, Ste. 202
City/State/Zip: Wichita, Ks 67214
Contact Person: Courtney Rogers
Phone: (316)-263-8588

150' S. East
SE. NE. SE. Sec. 17 Twp. 21 S, Rg. 13 X West
1500 Ft. from South Line of Section
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County: Stafford

CONTRACTOR: License # 5122
Name: Woodman-Iannitti Drilling Company Box 308
City/State: Great Bend, Ks 67530 316-792-1922

Lease Name: Reiser Well # 1
Ground surface elevation 1900 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 180'
Depth to bottom of usable water 220'

Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 240'

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.

Date 4/25/88 Signature of Operator or Agent David Brewer Title Agent

Conductor pipe required none
Projected Total Depth 3700 feet

For KCC Use:

Formation Arbuckle

Conductor Pipe Required 10-25-88 feet Minimum Surface Pipe Required 240 feet per Alt. X

This Authorization Expires 4-25-88 Approved By 4-25-88

EFFECTIVE DATE: 4-25-88

SPUD 4-27-88 878.300'

yes w/w

150' S. East
SE. NE. SE. Sec. 17 Twp. 21 S, Rg. 13 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... Top of Arbuckle... or formation with... feet of... 20. sks, 60-40. pas, 2% gel
2nd plug @ ft. deep... Top of Anhydrite... or formation with... feet of... 20. sks, 60-40. pas, 2% gel
3rd plug @ ft. deep... 50' below bottom of surface... or formation with... feet of... 40. sks, 60-40. pas, 2% gel
4th plug @ ft. deep... 40'... or formation with... feet of... 10. sks, 60-40. pas, 2% gel
5th plug @ ft. deep... or formation with... feet of...

(2) Rathole to surface minus 5 feet 10 sks, 60-40 pas, 2% gel (b) Mousehole to surface minus 5 feet

PUSHER Rich Whallas
TD 3729 FORMATION Arb. 3683
SURFACE PIPE 8 3/8 @ 302
ANHYDRITE 809 ELEVATION
STARTING TIME & DATE 6:00AM 5-5-88
COMPLETION TIME & DATE 7:45AM 5-5-88
1st PLUG @ 50' below surface FT. WI 25 SX
2nd PLUG @ 810 FT. WI 50 SX
3rd PLUG @ 330 FT. WI 50 SX
4th PLUG @ 40-0 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI SX
WATER WELL PLUGGED WI 10 SX
CEMENT COMPANY called
P.A. Technician

60 x 40 w/ 6% gel

RECEIVED STATE CORPORATION COMMISSION

MAY 06 1988

CONSERVATION DIVISION Wichita, Kansas