

15.185.21680.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,680

SE/4, Sec. 17, T 21 S, R 13 W/1

190 feet from N/S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name VINK Well # 1

Operator: Globe Exploration, Inc

County Stafford

Name & Address Great Bend, KS 67530

Well Total Depth 3703 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 301'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exp. Co. Inc. License Number 5652-229

Address Box 1425, GREAT BEND, KS 67530

Company to plug at: Hour: 2:00pm Day: 1 Month: NOV Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Jim Overbey

(company name) Mustang (phone) 316-792-6877

were: use 50/50 Pozmix-4% gel -3% C.C.

1st Plug @ 720' w/60sf

2nd Plug @ 330' w/40sf

3rd Plug @ 40' w/solid bridge of hulls & wood Plug

4th Plug 40'-0' w/10sf cement, Rathole w/10sf

circulated.

Signed R. B. Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45pm Day: 1 Month: NOV Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.

Cementing by Sun.

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION Wichita, Kansas

Remarks: 8 5/8 w/225sf 60/40 Pozmix, 4% gel -3% CC

anhydrite @ 781

Water well retained by farmer

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging. Observed by J.H. Metz

Signed R. B. Barluttan (TECHNICIAN)

INVOICED
DATE 12-30-82
INV. NO. 1901-w

FORM CP-2/3 Rev. 9-82