

1 080348

15.185.19558.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 10-20-62

SW NE NW, SEC. 17, T 21 S, R 13 WEX

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Harms "F" Well # 2

Operator: Petroleum, Inc.  
Name & Address: P. O. Box 1447  
Great Bend, KS 67530

County Stafford 118.95

Well Total Depth 3660 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 332 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 am Day: 21 Month: March Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" set at 3657' Perfs at 3406-11; 3359-62; 3343-46'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging orders given by Paul A. Luthi

Plugging Proposal Received by J. A. Muf (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 am Day: 21 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dump 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 25 1985

Maximum pressure 300 psi and shut in 100 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 1000' 5 1/2" casing. Used 60/40 Pozmix 4% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did / x) observe this plugging.

DATE 3-26-85

Signed J. A. Muf (TECHNICIAN)

INV. NO. 7452