

10-23-87

To: 1 050948  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,365  
C SW, SEC. 13, T 21 S, R 18 W/E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5278

Lease Name Lucas A Well # 1-13

Operator: Enron Corporation  
Name & Address P.O. Box 2267  
Midland, TX 79702

County Pawnee 6793  
Well Total Depth 2090 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 830

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8 a.m. Day: 23 Month: 10 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 2089' PBTD 2083'

1st plug pump 1 sx hulls and 20 sx cement to 2076',

2nd plug pump 40 sx cement at 1200',

3rd plug pump 40 sx cement at 860',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:45 a.m. Day: 23 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to 2076',

2nd plug pumped 40 sx cement at 1200',

3rd plug pumped 40 sx cement at 860',

4th plug pumped 10 sx cement at 40'.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1420' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-30-87

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 18724