

9-7

API NUMBER 15- 145-20,362-0000

C NE/4, SEC. 13, T 21 S, R 18 W/X

3960 feet from S section line

1320 feet from E section line

Lease Name Lucas Well # 1-13

County Pawnee 70.04

Well Total Depth 2155 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 828

To: 1 070585
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco Inc.

Name & Address 970 Fourth Financial Center

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address Box 346, Ness City, KS 67560

Company to plug at: Hour: 2:30 p.m. Day: 7 Month: 9 Year: 19 88

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

were: 4 1/2" at 2154' PBTD 2141' Perfs at 2104-36'

1st plug sand bottom 50' above the perfs and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1988

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Wichita, Kansas Hour: 3:30 p.m. Day: 7 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 2050' and dump 4 sx cement on top of

sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and

150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1513' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

~~(If desired, you may wish to observe this plugging.)~~

INVOICED

Signed Dan Johnson
(TECHNICIAN)

DATE 9-15-88

INV. NO. 22274