

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec 17 Twp. 21S Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW

Lease Owner Fred Shaffer

Lease Name Fischer Well No. 1

Office Address Hutchinson, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 8 19 64

Application for plugging filed May 19 66

Application for plugging approved May 19 66

Plugging commenced May 16 19 66

Plugging completed May 23 19 66

Reason for abandonment of well or producing formation Not producing;

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 3714 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back with gravel to 3600', and dumped 5 sacks of cement. Shot pipe off at 1917.75'. Pulled pipe and mudded hole to 321'. Set 15' rock bridge and dumped 6 sacks of cement; let set 48 hours and bailed hole dry and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge and dumped 10 sacks of cement at base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 25th day of May 19 66

My commission expires October 15, 1969

Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves & Petroleum, Inc. DRILLING COMMENCED: November 9, 1962  
 CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: November 18, 1962  
 CASING RECORD: 11 jts. 332.03' of 8-5/8" w/ 325 sx. cement LOCATION: Fischer "E" No. 2  
 NW SE NW  
 Section 17-21S-13W  
 Stafford County, Kansas  
 ELEVATION: 1916 feet, Kelly Bushing

0 - 80 Sand, shale & lime  
 80 - 290 Shale & sand  
 290 - 330 Red bed & shale  
 330 - 1533 Shale  
 1533 - 1760 Shale & lime  
 1760 - 1905 Lime & shale  
 1905 - 2165 Lime  
 2165 - 2257 Shale & lime  
 2257 - 3010 Shale  
 3010 - 3075 Shale & lime  
 3075 - 3170 Lime & shale  
 3170 - 3560 Lime  
 3560 - 3573 Shale  
 3573 - 3604 Lime  
 3604 - 3662 Shale  
 3662 - 3682 Lime & Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 29 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves  
President

STATE OF KANSAS )  
                          ) SS  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 28th day of November, 1962.

My commission expires Apr. 22, 1963

Betty Brandt  
Notary Public