

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 7 Twp. 21S Rge. (E) 18 (W)

Location as "NE/CNW%SW%" or footage from lines 50' W of Center NE-NE

Lease Owner The Pure Oil Company

Lease Name Malvin Ford Well No. 1

Office Address PO Box 9545 Okla. City 18, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 19, 1960

Application for plugging filed December 19, 1960

Application for plugging approved December 19, 1960

Plugging commenced December 19, 1960

Plugging completed December 19, 1960

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation None Depth to top - Bottom - Total Depth of Well 4392 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	500'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dry Hole - 8-5/8" casing set at 500' with 300 sack. Hole full of rotary mud to 350' from surface. Set wood plug & 1/4 sack hulls 350-280', filled with rotary mud from 280 to 35' from surface, set wood plug, 1/4 sack hulls, & 10 sack cement from 35' to surface, filled cellar with soil 1' to surface. Put 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
1-19-61
JAN 19 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Wichita, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
C. C. Lutz (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 9545 Okla. City 18, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 1961

My commission expires 4-14-64 John C. Stallard Notary Public.

WELL LOG

15.145.00423.0000

COMPANY PURE OIL COMPANY

SEC. 7 T. 21S R. 18W

FARM FORD NO. 1


LOC. C-NE, NE

TOTAL DEPTH 4392'

COUNTY PAWNEE CO., KANSAS

COMM. December 6, 1960 COMP. December 20, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 500' w/300 sax.

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

FILED
STATE OF KANSAS COMMISSION

JAN 13 1961

CONSERVATION DIVISION
Wichita, Kansas

350	Shale & shells
500	Shale & clay
800	Red bed
1184	Shale
1206	Anhydrite
1625	Shale & shells
1900	Sand
2100	Shale
2180	Lime & shale
2345	Lime
3048	Lime & shale
3230	Lime
3360	Shale & lime
3435	Lime & shale
3637	Lime
3673	Lime & shale
3787	Lime
3834	Lime & shale
3880	Lime
4223	Lime & shale
4374	Lime, shale & chert
4392	Lime & chert
4392	T. D.

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 FORD well

Verne A. Morris.

Subscribed and sworn to before me this 29th day of December 19 60

My Commission Expires: November 12, 1962

[Signature]
NOTARY PUBLIC

WELL LOG AND RELATED DATA

DIVISION Northern Producing DISTRICT Central (Buffalo-Kansas) LEASE Ford, Malvin
 ACRES 360 LEASE NO. 50147 AFE NO. 2752 ELEVATION Grd. 2091', D.F. 2098' WELL NO. 1
 TWP. 21S RGE. 18W PRCT.-DIST.-TWP. -
 SURVEY (S.E. Oro Prospect) COUNTY Pawnee STATE Kansas

LOG			
FROM	TO	TOTAL	FORMATION
(Sample Data starts @ 500')			
0	350	350	Shale & shells
350	500	150	Shale & clay
500	3592	3092	Sand, shale & lime
3592	LANSING-KANSAS CITY (Geol. Top)		
3592	3980	388	Lime & shale
3980	MARMATON (Geol. Top)		
3980	4078	98	Lime, cream-tan, dense, crystalline lime & shale
4078	ARBUCKLE (Geol. Top)		
4078	4392	314	Lime, white-brown, crystalline-dense, cherty in part & streaks of shale
4392	TOTAL DEPTH		

(All measurements taken from top of rotary bushing which is 2' above derrick floor)

STATE COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas
 JAN 13 1961

LOCATION

1620 FEET NORTH OF SOUTH SECTION LINE
 4570 FEET EAST OF WEST SECTION LINE
 660 FEET SOUTH OF NORTH SECTION LINE
 710 FEET WEST OF EAST SECTION LINE

SCALE 2"=1 MILE

CASING AND CEMENTING RECORD						
SIZE CASING	8-5/8"					
THREAD	8rd.					
WEIGHT	24#					
GRADE	J-55					
CONDITION	C/A					
SET AT	500'					
SACKS CEMENT	300					
SIZE OF HOLE	12-1/4"					

LINER RECORD						
SIZE	WT.	COND.	LENGTH	BLANK	PERF.	SET AT

GUN PERFORATING RECORD					
DATE	CASING	FROM	TO	SIZE SHOTS	NO. SHOTS

SHOT OR ACID RECORD				
DATE	TOP	BOTTOM	SHOT-ACID	REMARKS

DRILLING: COMMENCED 12-6-60 COMPLETED 12-19-60
 ELECTRICAL SURVEY BY Schlumberger (Later Sigsbee & Sons) 12-19-60
 DRILLED WITH (Garvey Drilling Co.) Rotary TOOLS
 DRILLED IN WITH (Garvey Drilling Co.) Rotary TOOLS
 DRILLED IN WITH Dry Hole
 FIRST PROD.—NAT. DATE _____ HRS. _____ BBLs. _____ OIL
 WATER _____ M CU. FT. GAS _____ LBS. ROCK PRESS.
 SHOT
 FIRST PROD. AFTER ACID—DATE _____ HRS. _____ BBLs. _____ OIL
 WATER _____ M CU. FT. GAS _____ LBS. ROCK PRESS.
 GAS/OIL RATIO _____ POTENTIAL Dry Hole BBLs. _____
 GRAVITY _____ TEMP. _____ GRADE _____

