

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Pitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above Section Plat

County, Sec. 19 Twp. 21 Rge. 17 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Honaker Drlg., Inc.  
Lease Name Jordaan Well No. 1  
Office Address 2008 Lakin Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-23 19 55  
Application for plugging filed 7-23 19 55  
Application for plugging approved Telephone 7-23 19 55  
Plugging commenced 12:30 A. M. 7-23 19 55  
Plugging completed 1:30 A. M. 7-23 19 55  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4043 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	309'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled Hole with Heavy Rotary Mud to top of pipe. Used one plug with 100 sacks cement - pumped in at approximately 300# pressure by Globe Oil Cementing Co.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker Drlg., Inc.  
Address 2008 Lakin Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Bill Edwards (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Edwards

2008 Lakin Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of July, 19 55

My commission expires 6-25-59

24-7366-5 3-53-20M

**RECEIVED**  
STATE CORPORATION COMMISSION Notary Public.

AUG 9 X 1955

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC. 19 Twp. 21 Rge. 17 W  
BOOK PAGE 137 LINE 8

DRILLERS LOG

Jordann No. 1  
 Loc: NE NE NE  
 Sec: 19-21S-17W  
 Pawnee County, Kansas  
 Company: Honaker Drig., Inc. et al  
 Contractor: Honaker Drig., Inc.

Commenced 7-7-55  
 Completed 7-21-55  
 Rotary Total Depth: 4043'  
 Casing: 8-5/8" at 310'  
 D & A

0	40	Clay & Sand	
40	125	Clay	
125	275	Sand	
275	415	Blue Shale	
415	480	Red Bed	
480	620	Sand	
620	1060	Shale & Shells	
1060	1092	Anhydrite	8-5/8" casing cemented
1092	1400	Shale & Shells	at 310' with 225 sacks
1400	1475	Salt & Shale	cement and 4 sacks
1475	1920	Shale & Shells	calcium chloride
1920	2770	Lime & Shale	
2770	3170	Shale & Lime	
3170	3391	Lime & Shale	
3391	3492	Shale & Lime	
3492	3784	Lime & Shale	
3784	3854	Shale & Lime	
3854	3892	Lime & Shale	
3892	3926	Chert & Shale	
3926	3937	Lime & Shale	
3937	4043	Chert & Shale	
4043	4043	Total Rotary Depth	D & A

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

*H. S. Forbes*  
 \_\_\_\_\_  
 H. S. Forbes

Subscribed and sworn to before me this 28th day of July, 1955.

**PLUGGING**  
 FILE SEC 19 T 21 R 17W  
 BOOK PAGE 137 LINE 8

*Kenneth G. Fisher*  
 \_\_\_\_\_  
 Kenneth G. Fisher, Notary Public  
 STATE CORPORATION COMMISSIONER

My Commission Expires: 6-25-59  
 AUG 9, 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas