

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 19 Twp. 21S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
C NE NW

Lease Owner Beren Corporation
Lease Name Gore #2 Well No. 2

Office Address 970 Fourth Financial Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole

Date Well completed December 10, 1977 19
Application for plugging filed December 10, 1977 19
Application for plugging approved December 10, 1977 19
Plugging commenced 2:00 PM, December 10, 1977 19
Plugging completed 3:30 PM, December 10, 1977 19
Reason for abandonment of well or producing formation
Dry Hole



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2145'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	317'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Pumped thru open end drill pipe
35 sacks at 420'; 20 sacks at 240';
solid bridge at 40' with 1/4 sack bulls
and plug; 10 sacks to surface.

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. **STERLING DRILLING COMPANY**

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 12th day of December, 19 77

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.



15.145.20494.0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG -----2----- GORE #2
Located: C NE NW, Section 19-21S-17W, Pawnee County,
Kansas

OWNER: Beren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 3, 1977
COMPLETED: December 10, 1977

TOTAL DEPTH: 2145'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 330	Clay and Shale	Ran 11 joints 7", 20# used casing, 315' cemented at 317' G.L. with 150 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:30 AM, 12-4-77.
330 - 920	Sand and Shale	
920 - 1085	Shale	
1085 - 1110	Anhydrite	
1110 - 1315	Shale	
1315 - 1817	Lime and Shale	
1817 - 1930	Shale	
1930 - 2050	Lime and Shale	
2050 - 2092	Shale	
2092 - 2145	Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1977

CONSERVATION DIVISION
Wichita, Kansas