


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitter Building  
Wichita, Kansas

Pawnee County. Sec. 20 Twp. 21 Rge. 16 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines SE SE SE  
Lease Owner Musgrove Petroleum Corporation,  
Lease Name BICK Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 6, 1953  
Application for plugging filed September 6, 1953  
Application for plugging approved September 6, 1953  
Plugging commenced September 6, 1953  
Plugging completed September 6, 1953  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1004	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 300' with 20 sacks cement  
Set top plug at 40' with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation,  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I, GORDON L. KOELLING (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September 19 53

My commission expires September 24, 1956

Thomas L. Steinmeyer  
Notary Public.

24-7868-5. 3-53-20M  
STATE CORPORATION

9-17-53

PLUGGING  
FILE SEC 20 T 21 R16W  
BOOK PAGE 127 LINE 20

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Dick #1  
 LOCATION: SE SE SE Sec. 20-21-16  
 Pawnee County, Kansas.  
 COMMENCED: August 27, 1953  
 COMPLETED: September 6, 1953

0	60	Surface clay
60	105	Sand
105	262	Shale & shells
262	430	Shale
430	540	Sand
540	655	Red bed
655	710	Red bed & pyrite
710	990	Red bed & shale
990	1004	Lime, shells & shale
1004	1024	Anhydrite
1024	1755	Shale
1755	3508	Lime & shale
3508	3940	Lime
	3940	Rotary Total Depth

Set 8-5/8" surface pipe at 1004' with 425 sacks cement.

Dry and abandoned.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the DICK #1, SE SE SE Section 20-21-16, Pawnee County, Kansas, as reflected by the files of Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 15th day of September, 1953.

*Walter L. Stencamp*  
 Notary Public

My commission expires September 24, 1956.

**PLUGGING**  
 WELL SEC 20 T 21 R 16W  
 BOOK PAGE 127 LINE 20