


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Pawnee County, Sec. 36 Twp. 21S Rge. (X) 15(W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Peninsula Exploration Company
Lease Name Phinney Well No. 1
Office Address 1501 Guaranty Bank Plaza, Corpus Christie, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 11, 19 74
Application for plugging filed March 11, 19 74
Application for plugging approved March 11, 19 74
Plugging commenced March 11, 19 74
Plugging completed March 11, 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 3855 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	314'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Put plug in surface pipe and squeezed 100 sacks common cement through swedge with 400# pressure. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 19 74

My commission expires May 9, 1975

Betty Brandt
Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Peninsula Exploration Co. DRILLING COMMENCED: March 1, 1974
 1501 Guaranty Bank Plaza
 Corpus Christie, Texas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 11, 1974
 505 Union Center
 Wichita, Kansas 67202

CASING RECORD: 12 Jts. 314' 8-5/8" LOCATION: Phinney No. 1
 cemented with 250 sacks NE SW NE
 Section 36-21S-15W
 Pawnee County, Kansas

0 - 180	Sod & sand
180 - 315	Clay & shale
315 - 405	Shale & sand
405 - 1130	Red bed & shale
1130 - 1685	Shale & shells
1685 - 1758	Lime & shale
1758 - 1880	Lime
1880 - 2862	Lime & shale
2862 - 3025	Shale & lime
3025 - 3327	Lime
3327 - 3432	Shale
3432 - 3633	Lime
3633 - 3720	Lime & shale
3720 - 3730	Chert
3730 - 3770	Lime
3770 - 3822	Shale & lime
3822 - 3855	Lime
3855	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 14 1974
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves President

STATE OF KANSAS)
) ss.
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 12th of March, 1974.

My commission expires:
 May 9, 1975

Betty Brandt
 Betty Brandt Notary Public