


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
214 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 36 Twp. 21 Rge. 15 (E) 15 (W)
Location as "NE/CNW%SW%" or footage from lines NE SE NW
Lease Owner Thos. H. Allan, et al
Lease Name Yeager Well No. 1
Office Address 925 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Lost Hole
Date ~~well~~ ^{lost hole} completed January 24, 19 59
Application for plugging filed January 24, 19 59
Application for plugging approved January 24, 19 59
Plugging commenced January 24, 19 59
Plugging completed January 24, 19 59
Reason for abandonment of well or producing formation Lost Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2985 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	397'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2985 - 250 Heavy Rotary Mud
250 - 175 Bridge of Halliburton Plug, sack of hulls, rock, & 20 sacks of cement
175 - 35 Mud
35 - Surface Bridge of Halliburton Plug, sack of hulls, rock & 10 sacks of cement

NOTE: Abandoned hole due to bottom joint of 8 5/8" Casing came off and plugged hole at 900 feet deep.

Skidded rig 120 feet north and started new hole.

RECEIVED

STATE CORPORATION COMMISSION

JAN 28 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thos. H. Allan
Address 925 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
THOS. H. ALLAN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thos. H. Allan
925 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 59

Osie M. Stewart
Notary Public.

My commission expires June 14, 1962

PLUGGING
FILE SEC. 36 T. 21 R. 15 W
BOOK PAGE 13 LINE 33

8 5/8" @ 397' - 200 Sx.

ALLAN - #1 YEAGER
NE SE NW 36-21-15W
Pawnee County, Kansas
COMM: 1/15/59 COMPL: 1/24/59
ELEV: 1961 RB
CONTRACTOR: Tom Allan

I.P. Abandoned

All Depths From Rotary Bushings

- 0 - 20 Soil
- 80 Coarse Sand
- 95 Yellow Clay
- 170 Sandy Clay
- 310 Yellow Clay & Lime Shells
- 397 Red Beds
- 912 Red Shale
- 936 Anhydrite
- 1200 Red Shale
- 1400 Shale
- 1700 Salt & Shale
- 1900 Shale & Anhydrite
- 2000 Shale
- 2150 Lime
- 2300 Shale & Shells
- 2400 Lime
- 2450 Shale
- 2550 Lime
- 2985 (T.D.) Shale
- Lost Hole
- Bottom joint of surface casing plugged hole at 900 ft. deep.

I certify that this is a true and correct copy of the well log.

Tom H. Allan

Subscribed and sworn to before me this 27th day of January, 1959

Osie M. Stewart

My commission expires June 14, 1962.

RECORDED
STATE COMMISSION
JAN 28 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 36 T 21 R 15W
BOOK PAGE 13 LINE 33