

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County. Sec. 10 Twp. 21S Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Tilco, et al

Lease Name Sinclair Well No. 1

Office Address 200 Sutton Place, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-5 19 69

Application for plugging filed 6-5 19 69

Application for plugging approved 6-5 19 69


Plugging commenced 6-5 19 69

Plugging completed 6-5 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4434 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	290'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 85 sacks cement @ 500'
Plugged with with 1/2 sacks hulls @ 45' 15 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1969

My commission expires April 1, 1971
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	SINCLAIR #1
LOCATION	C NW NW SECTION 10-21S-26W HODGEMAN COUNTY, KANSAS
COMMENCED	5-26-69
COMPLETED	6-5-69

0	155	Shale, Sand
155	290	Shale
290	830	Shale, Sand
830	1041	Red Bed, Sand
1041	1055	Anhydrite (Blain)
1055	1128	Red Bed
1128	1345	Sand
1345	1638	Red Bed, Shale
1638	1685	Anhydrite
1685	2320	Sahle, Shells
2320	2510	Lime, Shale
2510	3085	Lime
3085	3270	Lime, Shale
3270	3375	Lime
3375	3747	Lime, Shale
3747	4434	Lime
	<u>4434</u>	<u>RTD - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" 20# new surface casing set @ 290' cemented with 200 sacks
Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sinclair #1 Well, located C NW NW Section 10, Township 21 South, Range 26 West, Hodgeman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
)
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 9th day of June, 1969.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1971