


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 13 Twp. 21S Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NE
Lease Owner Koch Exploration Company
Lease Name Clifton Well No. 1
Office Address P. O. Box 2256, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed February 12, 19 69
Application for plugging filed February 12, 19 69
Application for plugging approved February 12, 19 69
Plugging commenced February 12, 19 69
Plugging completed February 12, 19 69
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4495' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	312 90'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with 80
sx @ 800' to 600',
35 sx @ 300' to 200',
15 sx @ 45' to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Norman E. Klein (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Norman E. Klein
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 19 69

Gloria Sawcitt

Notary Public.

My commission expires 10-25-72



DRILLERS LOG

No. 1 Clifton

CASING RECORD:	COMPANY:	Koch Exploration Co.	DESCRIPTION:
8 5/8" @ 320' w/200 Sx cement	CONTRACTOR:	Red Tiger Drilling Co.	SE NE 13-21S-26W Hodgeman County, Kansas
	COMMENCED:	January 31, 1969	
	COMPLETED:	February 12, 1969	
TOTAL DEPTH: 4495'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Shells	0	680	
Red Bed & Shale	680	970	
Blane	970	997	
Red Bed & Shale	997	1092	
Sand	1092	1300	
Red Bed & Shale	1300	1606	
Anhydrite	1606	1643	
Shale w/ Lime	1643	3090	
Shale, Lime, Shells	3090	3285	
Lime & Shale	3285	3410	
Shale & Chalky Lime	3410	3525	Topeka 3410
Shale & Lime	3525	3574	
Lime	3574	3741	
Shale	3741	3744	
Lime	3744	4185	
Lime & Shale	4185	4286	
Lime	4286	4420	
Conglomerate	4420	4430	
Lime & Shale	4430	4480	
Mississippi	4480	4495	

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 13th day of February, 1969.



Gloria Fawcett
Notary Public

10-25-72